

EQUIPMENT QUOTATION

Date: January 31, 2018
 To: Sef Alcazar
 CITY OF CULVER CITY
 From: Thom Prevost
 Project: The Culver City Municipal Plunge

| SECTION | QTY | DESCRIPTION | PRICE EACH | EXTENDED TOTAL |
|-------------------------------|-----|--|--------------------|--------------------|
| Filter Tanks | 2 | EPD 13.5 square foot fiberglass reinforced plastic high rate sand filter tank with internal components, includes Victaulic couplings, #20 Mesh silica sand, 100lbs bags | 9,591.00 | 19,182.00 |
| Filter Backwash Valves | 2 | EPD 4" backwash valve assembly, bronze coated, hydraulic activated 3-way valve externally coated with polyurethane | 1,306.00 | 2,612.00 |
| Pressure Amplification System | 1 | Pressure Amplification System, 1/2 HP pump with pressure sustaining tank, pressure switch and pump foot, inline strainer with 3/8" connection | 1,460.00 | 1,460.00 |
| Manual Backwash Controller | 1 | Semi-Automatic filter backwash controller for five (8) tank EPD system, and solenoid assembly | 1,357.00 | 1,357.00 |
| Installtoin | 1 | <p>Furnish labor and materials to replace (2) existing EPD filter tanks with (2) direct replacements EPD filter tanks as follows:</p> <p>Demolition: Removal and disposal of two (2) existing backwash valves, and one (1) existing backwash controller, remove and dispose of existing Victaulic couplings.</p> <p>Installation: Place (2) direct replacement EPD filter tanks in existing tank location including new tank anchors Reconnect new tanks to the existing influent and effluent manifolds complete with Victaulic couplings Install (2) new backwash valves complete with Victaulic couplings Load two (2) filter tanks with media, Install new pressure amplification system and new manual filter backwash controller, Start up system and test for proper operation</p> | 15,543.00 | 15,543.00 |
| | | | Subtotal | \$40,154.00 |
| | | | Sales Tax (10.00%) | \$2,461.10 |
| | | | Estimated Freight | \$1,294.19 |
| | | | Total | \$43,909.29 |

Terms and Conditions

- Payment:** Net 30 days after date of invoice
Quoted equipment will not be subject to project retention and invoices must be paid in full
- Interest:** 18% APR is charged on all past due invoices
- Returns:** Returns MUST be pre-approved, shipped prepaid and accompany written return authorization
- Restock:** A MINIMUM 20% restock fee applies to all returns; % is based on actual manufacturer restock fee
- Freight:** F.O.B. ship point, refer to estimated freight costs above
- Sales Tax:** Subject to sales tax rate as noted above
- Notes:** Pricing is valid until February 28, 2018
Verification of equipment items & quantities is the sole responsibility of the customer
Pricing excludes Health Department plan check fees, Payment / Performance / Bid Bond fees and Insurance Certificates.
All labor rated quoted meets current California DIR and Prevailing Wage requirements.
- Commissioning:** Mechanical equipment commissioning is provided at no charge by KSI's Service Department
On-site equipment commissioning is determined by size/type equipment provided.
- NOTE: KSI's start up work does NOT include electrical, plumbing, equipment installation, etc.