



www.knorrsystems.com

## **EQUIPMENT QUOTATION**

Date:

December 9, 2016

To:

Sef Alcazar

CITY OF CULVER CITY

From:

Thom Prevost

Project:

Municipal Plunge Filter System

SECTION	QTY	DESCRIPTION	PRICE EACH	EXTENDED TOTAL
Filter Tanks	2	EPD 17 square foot fiberglass reinforced high rate sand filter tank with internal components, includes Victaulic couplings	8,993.00	17,986.00
Filter Backwash Valves	4	EPD 4" backwash valve assembly, bronze coated, hydraulic activated 3-way valve externally coated with polyurethane	1,306.00	5,224.00
Filter Media	44	#20 Mesh silica sand, 100lb bag.	15.00	660.00
Installation	1	Furnish labor and materials to replace two existing EPD filter tanks with the above proposed filter tanks as follows:  Demolition: Temporarily support the filter controller bracket, remove and dispose of Victaulic couplings, existing tanks and backwash valves, cut the existing anchors flush to the service pad  Installation: Place the above proposed filter tanks in the existing tank location, reconnect tanks to existing manifold with new Victaulic couplings, install new backwash valves, install new filter leg anchors, fill filters with new filter media, start system up and test for proper operation	10,212.00	10,212.00
	L		Subtotal	\$34,082.00
			Sales Tax (9.5%)	\$2,267.65
			Estimated Freight	\$663.39
			Total	\$37,013.04